BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Providing Decorative / Ornamental / Pathway Lights with Poles in Parks and Footpaths and energy efficien street lights, real time street light control switches, control wires, poles ABC cable and other accessories in Ward No.01, 03 and 04

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. A N Madhusudhan (Suraksha Electrical	
				In figures	In words
1	186.47	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3) (V-I.No 1.4,Page No-5 PWD SR 2021-22)	Cum	214.81	Rupees Two Hundre Fourteen And Paise Eighty One Only
2	12.26	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates (V-1, P.No-15, I No-2.1.3 of PWD SR 2021-22)	Cum	6414.38	Rupees Six Thousan Four Hundred Fourteen And Paise Thirty Eight Only
3	10.17	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.(V-III, I.No 13.1 Page No 99, PWD SR 2021-22)	Tonne	106447.95	Rupees One Lakh Six Thousand Four Hundred Forty Seven And Paise Ninety Five Only
4	104.51	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (V-1.P.No.17, I.No.2.4.2 of PWD SR 2021-22)	Cum	7237.18	Rupees Seven Thousand Two Hundred Thirty Seven And Paise Eighteen Only
5	108.00	Providing and Fixing Pre cast covering Slab 100mm thick made out of CC, jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge.	Sqm	2175.44	Rupees Two Thousand One Hundred Seventy Five And Paise Forty Four Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

No	Quantity	Item Name	Unit	Approved Rates of Sri. A N Madhusudhan (Suraksha Electricals)	
				In figures	In words
6	522.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete ,complete.	Nos	532.30	Rupees Five Hundred Thirty Two And Paise Thirty Only
7	700.00	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mouting with outer dia of 40mm to 50mm Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by	Nos	8157.91	Rupees Eight Thousand One Hundred Fifty Seven And Paise Ninety One Only
8	80.00	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mouting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by	Nos	10497.11	Rupees Ten Thousand Four Hundred Ninety Seven And Paise Eleven Only
9	190.00	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mouting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by	Nos	14102.48	Rupees Fourteen Thousand One Hundred Two And Paise Forty Eight Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

No	Quantity	Item Name	Unit	Approved Rates of Sri. A N Madhusudhan (Suraksha Electricals)	
				In figures	In words
10	250.00	Supply of LED floodlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate/clear glass material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mouting with outer dia of 40mm to 50mm.Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/ IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption, LED Efficiency>130lm/w, nominal CRI	Nos	20994.12	Rupees Twenty Thousand Nine Hundred Ninety Four And Paise Twelve Only
11	700.00	Supplying and Fixing of.....mm dia class A GI pipe bracket upto 2 ms long bent at suitable angle and fixing to this bracket 1x40/2x40 W fluorescent tube street light fitting of all capacities to GI or GI or rail or RCC pole / wall using suitable clA, bolts, and nuts and wiring using suitable capacity wires.Using 32mm dia G.I.Pipe	Each	947.08	Rupees Nine Hundred Forty Seven And Paise Eight Only
12	40.00	Fabricating, supplying and erection of ...Mtrs long hot dip Galvanized Octagonal pole with BSEN 10025 grade S 355 JO steel plate for shaft, IS 2062 for base plate with door opening arrangements, including suitable boards, Bakelite sheet and MCBs as per IS specifications suitable to withstand the wind speed of 47 m/sec for .....Mtrs pole in single section and single joint welded as per IS 9595/IS 10178AWS having dimensions bottom .....mm, top....mm with 3mm thick, suitable base plate and 4Nos of long J bolts along with template and the pole shall be hot dip galvanized in single dipping with not less than 65micron as per ASTM-A123 and 153 etc., (excluding foundation) as per drawing appended.7 meters - Top 70mm and bottom 130mm dia	Nos	12636.81	Rupees Twelve Thousand Six Hundred Thirty Six And Paise Eighty One Only
13	40.00	Supplying, and fixing of Hot dip Galvanized M.S.Bracket suitable for out door luminaries and mounted on Octagonal pole using necessary bolts, nuts etc., complete.Double Arm Bracket with 1500mm Standard 40/50MM dia	Nos	3270.51	Rupees Three Thousand Two Hundred Seventy And Paise Fifty One Only
14	20.00	Fabricating, supplying and erecting swaged tubular pole of height ...Mtr having three sections, and providing two coats of red oxide paint and finished with two coats of enamelled paint of approved quality and colour and M.S. base plate of suitable size welded at the bottom of the pole(as per IS) and 40mm dia GI / flexible PVC pipe of 1 mtr length fitted to the heavy gauge polycarbonate control box including 5way connector of size 167x125x82mm for 7.5M pole/200x160x98mm for remaining length of pole with front opening cover, with locking arrangements and suitable capacity MCB / DP switch. The pole shall be erected in cement concrete work (1:2:4) including excavation and refilling of planting depth of the pole to the ground level and the coping CC shall be up to 0.6M above ground level as per IS 2713 - 7.Erection of heavy duty pole on Footpath / median 10Mt (5Mt Hb,165.1mm dia 4.85mm thick x3M Hm, 139.7mm dia 4.50mm thick x 2M Ht,114.3mm dia 3.65mm thick) as per IS 410 SP 47	Each	18019.69	Rupees Eighteen Thousand Nineteen And Paise Sixty Nine Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

No	Quantity	Item Name	Unit	Approved Rates of Sri. A N Madhusudhan (Suraksha Electricals)	
				In figures	In words
15	20.00	Supplying and fixing telescopic M.S. bracket fabricated by using 0.5m length 4" dia telescopic M. S. pipe, with 2" dia 1.5m long M. S. bracket and are welded with suitable angle, using 6mm thick M. S. sheet, grip bolts & nuts, as required, suitable for 9 to 12 Mtrs. M. S. tubular pole, with necessary two coats of painting, with all other accessories.Single bracket 1.5 Mtr. Length	Each	1360.78	Rupees One Thousand Three Hundred Sixty And Paise Seventy Eight Only
16	4.50	Supplying of 1.1 kV, XLPE or Heat resistant PVC insulated, PVC exutruted Inner Seath Armoured LTUG Cable as per IS-1554 (Part1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975 16 Sqmm, 4 Core, (11 GI Strips - 4 x 0.8 mm)	Km	192599.01	Rupees One Lakh(s) Ninety Two Thousand Five Hundred Ninety Nine And Paise One Only
17	1.20	Supplying of 1.1 kV, XLPE or Heat resistant PVC insulated, PVC exutruted Inner Seath Armoured LTUG Cable as per IS-1554 (Part1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975 25 Sqmm, 3.5 Core, (12 GI Strips - 4 x 0.8 mm)	Km	190509.46	Rupees One Lakh(s) Ninety Thousand Five Hundred Nine And Paise Forty Six Only
18	0.50	Supplying of 1.1 kV, XLPE or Heat resistant PVC insulated, PVC exutruted Inner Seath Armoured LTUG Cable as per IS-1554 (Part1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975 35 Sqmm, 3.5 Core, (14 GI Strips - 4 x 0.8 mm)	Km	219086.10	Rupees Two Lakh(s) Nineteen Thousand Eighty Six And Paise Ten Only
19	5.70	Laying of cable in Existing Trench/GI pipe/Stone Ware/RCC Hume pipe using Wooden/Aluminum Rollers as directed by the departmental staff 2.5 to 25 Sqmm	Km	16965.56	Rupees Sixteen Thousand Nine Hundred Sixty Five And Paise Fifty Six Only
20	0.50	Laying of cable in Existing Trench/GI pipe/Stone Ware/RCC Hume pipe using Wooden/Aluminum Rollers as directed by the departmental staff 35 to 95 Sqmm	Km	24827.79	Rupees Twenty Four Thousand Eight Hundred Twenty Seven And Paise Seventy Nine Only
21	480.00	Earth work excavation for cable trench of 0.4 to 0.6 Mtr. Width and Depth upto 1 Mtr including trial pits, depositing on bank upto a lead of 50 Mtr, Supplying and Displaying necessary Danger Boards and Lighting, Using sight Rails and Sign Boards at every 100 Mtr wherever necessary as directed In Ordinary Soil	Cum	272.96	Rupees Two Hundred Seventy Two And Paise Ninety Six Only
22	480.00	Refilling the cable trenches with selected available earth from trench excavation including watering, consolidation in layers of 15 cm Thickness including depositing of the surplus earth with a lead of 200 Mtr	Cum	60.92	Rupees Sixty And Paise Ninety Two Only
23	1500.00	Supplying and drawing Flexible Multicore Cable manufactured with electrolytic grade flexible copper with low conductor confirming to IS:8130-1984 and (Virgin) PVC insulation sheathed suitable for working voltage upto 1100Volts as per IS-694:2010 4C X 1.5Sq.mm	Mtrs	92.40	Rupees Ninety Two And Paise Forty Only
24	50.00	GI Pipe B - Class as per IS-1239 GI Pipe - 40 mm Dia	Mtrs	309.69	Rupees Three Hundred Nine And Paise Sixty Nine Only
25	10.00	Supplying of Epoxy Terminating Kit (Pothead) suitable for 1.1 kV, LTUG Cable Up to 4C x 50 Sqmm	Nos	331.72	Rupees Three Hundred Thirty One And Paise Seventy Two Only
26	700.00	Supplying Heavy Duty Copper Terminal Long Barrel 25 Sqmm Copper Terminal, Apprx Wt. 11 Gm	Nos	30.36	Rupees Thirty And Paise Thirty Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. A N Madhusudhan (Suraksha Electricals)	
				In figures	In words
27	10.00	Rod type of earthing using 40 mm Dia, 3 Mtr long MS rod as ground rod, in earth pit of 300 mm width and 3300 mm depth and using 50x6 mm flat welded to ground rod as terminal & connected to equipment ground terminal using PVC Al wire as specified	Nos	2365.45	Rupees Two Thousand Three Hundred Sixty Five And Paise Forty Five Only
28	80.00	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. and M.S. flat ... with bolts, washers etc.,and painted with 2 coats of red oxide and then two coats of approved paint.40x40x6mm	Mtrs	288.92	Rupees Two Hundred Eighty Eight And Paise Ninety Two Only
29	350000.00	Fabricating supplying and mounting MS box made out SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 7tanks treatment with powder coated paint and finally finished with approved colour etc., complete16SWG	Sqmm	0.40	Rupees And Paise Forty Only
30	10.00	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts, necessary phase separators, handle and wiring complete. Protection of Overload and Short circuit in Thermal Magnetic Release. Micro processor release shall have Earth Fault as per IS-13947. (Icu=100% Ics). In 4P MCCB, all Poles should have protection for Short-Cicrcuit/Over Load. For Microprocessor MCCBS Facility for segregating Priority and Non-Priority loads must be available in the MCCB. MCCB shall be provided with double insulation (insulation between front cover and internal power circuits to avoid any accidental contact with live current carrying path with the front cover open). Multi-pole breakers shall be designed to break all the poles simultaneously and they shall have a single mechanism complete. FOUR Pole 100 A 25 kA	Nos	8677.56	Rupees Eight Thousand Six Hundred Seventy Seven And Paise Fifty Six Only
31	1410.00	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts, necessary phase separators, handle and wiring complete. Protection of Overload and Short circuit in Thermal Magnetic Release. Micro processor release shall have Earth Fault as per IS-13947. (Icu=100% Ics). In 4P MCCB, all Poles should have protection for Short-Cicrcuit/Over Load. For Microprocessor MCCBS Facility for segregating Priority and Non-Priority loads must be available in the MCCB. MCCB shall be provided with double insulation (insulation between front cover and internal power circuits to avoid any accidental contact with live current carrying path with the front cover open). Multi-pole breakers shall be designed to break all the poles simultaneously and they shall have a single mechanism complete. FOUR Pole 100 A 25 kA	Nos	198.43	Rupees One Hundred Ninety Eight And Paise Forty Three Only
32	31.00	Supplying & fixing of retrofit type - LED bulb.....W with OPAL acrylic diffuser comprising of LED source with CCT 6500 degree K, CRI> 70%, efficacy >80 lumen per watt,life> 25000 burning hours and Compliance to IS 10322/IEC 60598, LM 79 & LM 80. The LED are driven by HF electronic driver integrated in the system, with PF > 0.95, power loss should < 5% of lamp wattage , short circuit & open circuit protection to be integrated in the circuit, THD less than 20%,Life as per LM 79. The operating input voltage should be between 130 to 275 volts. BIS Approved and Tested by ABL/CPRI accredited laboratory with 2 years Warranty against any manufacturing defect working under standard electrical condition 18W, 6500K	Each	457.77	Rupees Four Hundred Fifty Seven And Paise Seventy Seven Only
33	31.00	Supplying Spiral Earth Electrode	Each	260.42	Rupees Two Hundred Sixty And Paise Forty Two Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. A N Madhusudhan (Suraksha Electricals)	
				In figures	In words
34	.00	Dismanting of Steel/I- Beam/Tubular poles (90% of the Pole erection charges.p2/2.01 Rs 688.00x90%=619.2)	Each	650.03	Rupees Six Hundred Fifty And Paise Three Only
35	190.00	Releasing of existing LEd street light(Fixing halogen/metal halide / SVL / IL / LED floodlight fitting over existing pole / wall ceiling including clamps, bolts, nuts and wiring using suitable capacity wires. (Releasing of LED Lights=90% of erction Charges Rs 189x90%=170.10)	Each	178.54	Rupees One Hundred Seventy Eight And Paise Fifty Four Only
36	150.00	Mobile Hydraulic Crane 35 t capacity for releasing and refixing of High Mast	hour	1835.30	Rupees One Thousand Eight Hundred Thirty Five And Paise Thirty Only
37	5.00	Supply of 1.1 kV, LT Aerial Bunched Cable, XLPE insulation confirming to IS-14255: 1995 3x25 + 1x25 + 1x16 Sqmm Street light (Insulated Messenger cum Neutral)	Km	208355.99	Rupees Two Lakh(s) Eight Thousand Three Hundred Fifty Five And Paise Ninety Nine Only
38	120.00	Piercing Connector Suitable for 16 Sqmm - 95 Sqmm AB Cable - Street Light Connection	Nos	191.08	Rupees One Hundred Ninety One And Paise Eight Only
39	10.00	Dead End Clamp/Anchor Clamp Assembly 25 to 95 Sqmm Bare Messenger(Exclusive of Pole Clamp and Eye Hook)	Nos	156.41	Rupees One Hundred Fifty Six And Paise Forty One Only
40	60.00	Suspension Clamp Assembly 16 to 70 Sqmm Bare Messenger (Exclusive of Pole Clamp and Eye Hook	Nos	226.78	Rupees Two Hundred Twenty Six And Paise Seventy Eight Only
41	5.00	Stringing of 1.1 kV grade Aerial Bunched 3 Core cable of XLPE insulation of size (3x95) (Phase Conductor) + (1x70) (Insulated Messenger Neutral) + (1x25) (Street Light Control)	Km	27128.79	Rupees Twenty Seven Thousand One Hundred Twenty Eight And Paise Seventy Nine Only
42	60.00	Erection of Suspension Clamp - 25 to 95 Sqmm bare messenger	Nos	153.28	Rupees One Hundred Fifty Three And Paise Twenty Eight Only
43	120.00	Installation of Insulation piercing connector for Main to Street Light Main : 16-95 Sqmm, Tap: 1.5-10 Sqmm (EP95)	Nos	71.40	Rupees Seventy One And Paise Forty Only
44	10.00	Fixing of Dead End Clamp	Nos	305.57	Rupees Three Hundred Five And Paise Fifty Seven Only
45	10.00	Centralized Control & Monitoring Sysem (CCMS) for Streetlights consisting of: Supply and erection of Thyristor based single phase smart streetlight control and monitoring system remotely control and monitorable smart streetlight system by using web or mbile application Remote lighting management based on Master control unit (MCU): handles controlling data handling other communication process. Commiunication units : GSM/GPRS Gate driver unit : for driving the Thyristor switching Thristor: SCR 106 Amps dual Thyristor moduel for switching Embedded firmware: firmware to control, handle, Process the data and communicate it wirelessly and IP 65 weather proof MS Enclosure.	Nos	72213.32	Rupees Seventy Two Thousand Two Hundred Thirteen And Paise Thirty Two Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. A N Madhusudhan (Suraksha Electricals)	
				In figures	In words
46	50.00	Supply and errection of Single phase 63 Amps Thyristor based Streetlight control system consisting of: micro controller based electronic Timer with RTC, 2x16 LCD with back light, 5 Tactile keys, 106 Thyristor module for load switching mouted on extruded aluminium heat sink, Thyristor driver card for switching Thyristor module, 2 numbers of 63 Amps MCB for over load protection and manual switching, 18 SWG CRACA MS sheet enclouser.	Nos	31287.52	Rupees Thirty One Thousand Two Hundred Eighty Seven And Paise Fifty Two Only
47	30.00	Supply and erection of 3 Mtr long Aluminium decorative Pole with 60 watt LED Light made out of single piece extruded alluminium 75x150mm with 3 MM thickness,self "U" type in built grove for strip lighting with same dimension attached Square arm of size 600x600mm curvature at the top with Two nos of Light, Blue/pinck colour Strip Light should be conduted along the Pole and Square light on liner side. Grey Colour Powder Coated, strip wattage 20W, pole is mounted on base Plate of 200x200 with required 4 nos foundation Bolts suitable for cable entry hole of 60mm at the bottom of the Pole. MCB Cutting of 500mm from the bottom of the pole with 12 inches Height.as per the Drawing enclosed . Model name & Make :Square super , Emerald Lighting Solutions or any equalent	Nos	42469.13	Rupees Forty Two Thousand Four Hundred Sixty Nine And Paise Thirteen Only
48	20.00	Supply and erection of 3 Mtr long Aluminium Pole with 60 watt LED Light made out of extruded alluminium 75x150mm with 3 MM thickness, with same dimention extended diamond shape bent at 45 deg Bracket, Diamond of size 400x780 mm Shaped Curvature suspended from the Bracket, Blue/pinck colour Strip Light should be conduted along the Pole, bracket and Diomend Shape on linear side, Grey Colour Powder Coated, strip wattage 20W, pole is mounted on base Plate of 200x200 with required 4 nos foundation Bolts,templates suitable for cable entry hole of 60mm at the bottom of the Pole. MCB Cutting of 500mm from the bottom of the pole with 12 inches Height.as per the Drawing enclosed. Model name & Make :Diamond Cargo , Emerald Lighting Solutions or any equalent	Nos	54956.88	Rupees Fifty Four Thousand Nine Hundred Fifty Six And Paise Eighty Eight Only
49	45.00	Supply and erection of 3 Mtr long Aluminium Pole with 60 watt LED Light made out of extruded alluminium 75x150mm with 3 MM thickness, self "U" type in built grove for strip lighting with same dimension extended Z tye bent arm Bracket and Blue/pinck colour Strip Light should be conduted along the Pole and bracket on liner side, Grey Colour Powder Coated, strip wattage 20W, pole is mounted on base Plate of 200x200 with required 4 nos foundation Bolts, templates suitable for cable entry hole of 60mm at the bottom of the Pole. MCB Cutting of 500mm from the bottom of the pole with 12 inches Height.as per the Drawing enclosed. Model name & Make :Krishi , Emerald Lighting Solutions or any equalent	Nos	39056.90	Rupees Thirty Nine Thousand Fifty Six And Paise Ninety Only
50	20.00	Supply of 3 Mtr Powder Coated Mild Steel Pole with 3mm thickness having top Triangle shape with light 36w and arm light 24w Body Colour Grey/Black . 3mtr pole will have blue colour 20w strip on double side of the pole. Square base Plate sized 250x250 welded at the bottom of the pole with required 4 nos foundation Bolts suitable for cable entry hole of 60mm at the bottom of the Pole. MCB access door cutting of 500mm from the bottom of the pole with 12 inches Height. Make : Emerald Lighting Solutions Model XENON X-VI or any equalent	Nos	45933.86	Rupees Forty Five Thousand Nine Hundred Thirty Three And Paise Eighty Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. A N Madhusudhan (Suraksha Electricals)	
				In figures	In words
51	40.00	Supply of 3 Mtr Powder Coated Mild Steel Pole with 3mm thickness having top Giraffe neck shape with light 36w and Body Colour Grey/Black . 3mtr pole will have blue colour 20w strip on double side of the pole. Square base Plate sized 250x250 welded at the bottom of the pole with required 4 nos foundation Bolts suitable for cable entry hole of 60mm at the bottom of the Pole. MCB access door cutting of 500mm from the bottom of the pole with 12 inches Height. Make : Emerald Lighting solutions Model GIRAFFEE or any equalent	Nos	45566.39	Rupees Forty Five Thousand Five Hundred Sixty Six And Paise Thirty Nine Only
52	25.00	Supply of 3 Mtr Powder Coated Mild Steel Pole with 3mm thickness having top Triangle shape, Arm will have 600mm length at one side PCB will be palced with 36w light output , Body Colour Grey/Black . 3mtr pole and top triangle fixture will have blue colour 20w strip on double side of the pole Square base Plate sized 250x250 welded at the bottom of the pole with required 4 nos foundation Bolts suitable for cable entry hole of 60mm at the bottom of the Pole. MCB access door cutting of 500mm from the bottom of the pole with 12 inches Height. Make : Emerald Lighting solutions Model TRIO or any equalent	Nos	47771.21	Rupees Forty Seven Thousand Seven Hundred Seventy One And Paise Twenty One Only
53	52.00	Supply of Pressure die Cast body housing landscape Round Light, dimensions Dia:600mm,Hight 430mm and mounting dia OD 60mm, LED Light having 60w output and Body colour Grey/Black. Make : Emerald Lighting solutions Model,LUNAR or any equalent	Nos	18898.50	Rupees Eighteen Thousand Eight Hundred Ninety Eight And Paise Fifty Only
54	31.00	Fabricating, Supplying and errection of decorative bent type Tuskar Conical Street light pole with hot dip Galvanized with BSEN 10025 grade S 355 JO Steel plate for shaft, IS 2062 for base plate with door opening arrangements, including suitable boards, Bakelite sheet for MCBs as per IS Specifications.suitable to with stand the wind speed. The total height of the pole 9 mtrs. The pole should have 2 nos of pole esthetically bent either side. The dimensions of the pole bottom 178 mm,at 9 mtrs height 70 mm 3mm thick and one number of 3 mtr height and 139.7 mm dia perforated pole having colour changing LED Fixture, inside as suitable to the Drawing and picture. The base plate size of 350mm x 350mm x 18 mm for poles and a common baseplate of 900x320x20 mm and the pole shall be galvanized with not less than 65 micron etc and finally finished with paint as required with two different colour. (With out foundation). As per the enclosed Drawing ,pictures and IS standards compleet set includes templat & 6 nos 24 mm x750mm anchor bolts.	Nos	122446.55	Rupees One Lakh(s) Twenty Two Thousand Four Hundred Forty Six And Paise Fifty Five Only
55	74.00	Fabricating, Supplying and errection of decorative Zig- Zag bent type Street light pole with hot dip Galvanized with BSEN 10025 grade S 355 JO Steel plate for shaft, IS 2062 for base plate with door opening arrangements, including suitable boards, Bakelite sheet for MCBs as per IS Specifications.suitable to with stand the wind speed. The total height of the pole 7 mtrs towards road and 5 Mtrs footpath between the pole V shaped MS/any decorativ laser cutting jolly work The pole should have 2 nos of pole esthetically bent either side. The dimensions of the pole bottom square pipr of 175x175x4mmx2 Mtrs length and above 2 mtrs a dia of 76.1x3.25mmx5Mtrs and 3 Mtrs. as suitable to the Drawing and picture. The base plate size of 350mm x 350mm x 16 mm the pole shall be galvanized with not less than 65 micron etc and finally finished with PU paint as required with two different colour. (With out foundation). As per the enclosed Drawing ,pictures and IS standards compleet set includes templat 4 nos M20 x750mm anchor bolts.	Nos	94230.03	Rupees Ninety Four Thousand Two Hundred Thirty And Paise Three Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. A N Madhusudhan (Suraksha Electricals)	
				In figures	In words
56	190.00	Supply, instalation testing and commissioning of LED RGB inground 10 to 12 watt uplighter for landscape,path lighting bush lighting & etc, made out of die-cast anti-corodal aluminium alloy for optimal thermal dissipation and top plate is made out of 316L marien grade ss,the LEDs should be high quality COB chips osram&bridgelux the beam angle of the fitting shall be narow,medium,wide or asymetric as per the requirment luminaire shall be complete with driver and capabal of operating at line voltage with out any separate power supply from 100 to 270 V AC,50 hz, power factor>0.9shall be IP 66 and ik06 rated life time should be at least L70:50000 burning hours at 50.c. Luminaire shall be confirming to BIS and shall be complete with all necessry accessories required for proper working of fixture including weather proof connection cables, water proof connector etc as required	Nos	9790.47	Rupees Nine Thousand Seven Hundred Ninety And Paise Forty Seven Only
57	190.00	Supply, instalation testing and commissioning of LED RGB inground 7 to 9 watt uplighter for landscape,path lighting bush lighting & etc, made out of die-cast anti-corodal aluminium alloy for optimal thermal dissipation the LEDs should be high quality COB chips Osram&bridgelux the beam angle of the fitting shall be narow,medium,wide or asymetric as per the requirment luminaire shall be complete with driver and capabal of operating at line voltage with out any separate power supply from 100 to 270 V AC,50 hz, power factor>0.9 shall be IP 66 and ik06 rated life time should be at least L70:50000 burning hours at 50c. Luminaire shall be confirming to BIS and shall be complete with all necessry accessories required for proper working of fixture including weather proof connection cables, water proof connector etc as required.	Nos	6220.76	Rupees Six Thousand Two Hundred Twenty And Paise Seventy Six Only
58	1500.00	Supplying and laying of copper 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable Armouring strip thickness in average +5% 4 core 6 sqmm copper cable	Mtrs	358.60	Rupees Three Hundred Fifty Eight And Paise Sixty Only
59	80.00	Fabricating, Supplying and errection of Garden speaker protective enclsoure of size H 91.55mmxL30.50mmxB30.50mm fabricated out of MS 1"1/8 L angle and 1" weld mesh with bolts, washers , nuts & etc; and painted with 2 coats of red oxide and then two coats of green/any approved enaml paint.	Nos	6037.02	Rupees Six Thousand Thirty Seven And Paise Two Only
60	156.00	Laying of UG Cables by trenchless technology by adopting horizontal boring & Drawing of cable including preparation at site With HDPE Pipe i) Normal soil 5/6" bore size	Mtrs	890.33	Rupees Eight Hundred Ninety And Paise Thirty Three Only
61		Applicable GST Charges			

Contractor

Executive Engineer
Project Division
Yelahanka Zone